7206
1029. k. 14
2
K London

AT A

GENERAL MEETING

OF THE

MASTER PLASTERERS,

CONVENED TO RECEIVE THE

REPORT OF THEIR COMMITTEE,

AT THE

White-Hart Tavern, High-Holborn,

MARCH 17, AND MAY 19, 1796,

WILLIAM ROBERTS in the Chair,

UNANIMOUSLY AGREED THE FOLLOWING TO BE

THE LIST OF PRICES,

KNOWING THEM TO BE FAIR AND EQUITABLE IN PROPORTION TO THE PRESENT COST.

Printed by W. WILSON, St. Peter's-Hill, Doctors'-Commons.

Entered at Stationers'-Hall.

MDCC XCVI.

MEASURED WORK.

		Per Yard. s.	d.
PUGGING on ſingle fir Laths, one Inch and a Half thick, with Lime, Sand, and Hair, meaſured, including the Timbers, . . .	at	1	2
Rough Render, . . .	at	0	3½
Circular rough Render, . .	at	0	4½
Render ſet, ...	at	0	6
Circular Render ſet, . .	at	0	8
Floated Render ſet . . .	at	0	8
Circular floated Render ſet, .	at	0	10½
Floated Render ſet to Groins, .	at	1	0

	Per Yard. s.	d.
Lathing only, with ſingle fir Laths, at	0	6
Lath and Plaſter, one Coat, with ditto, at	0	9
Circular Lath and Plaſter, one Coat, with ditto, . . . at	1	0
Lath and Plaſter ſet with ſingle fir Laths, ... at	1	0
Circular Lath and Plaſter ſet with do, at	1	4
Lath and Plaſter ſet to Groins, with ditto, ... at	1	6
Lath and Plaſter, two Coats, and ſet with ditto, ... at	1	2
Circular Lath and Plaſter, two Coats, and ſet with ditto, . . . at	1	6½
Lath and Plaſter, two Coats, and ſet to Groins with ditto, . . at	1	8
Floated Lath and Plaſter ſet with do, at	1	4
Circular floated Lath and Plaſter ſet with ditto, ... at	1	9

		Per Yard. s.	d.
Floated Lath and Plaſter ſet to Groins, with ditto, . . .	at	2	0
Baſtard Stucco on Brick, . .	at	1	2
Circular Baſtard Stucco on Brick,	at	1	4½
Baſtard Stucco on ſingle Laths, if outſide fronts, the Scaffold to be charged,	at	1	10
Circular Baſtard Stucco, with ſingle fir Laths, ...	at	2	5
Inſide Stucco on Brick, . .	at	1	10
Circular Stucco on Brick, . .	at	2	5
Inſide Stucco, with ſingle fir Laths,	at	2	4
Circular Stucco, with ſingle fir Laths,	at	3	1
Add extra for dados on the four laſt articles, ...	at	0	4
Add extra for Circular Dados, . .		0	5
Rough caſt on Brick, no Scaffold, outſide, ...	at	1	6

		Per Yard. s.	d.
Circular rough Caſt, on Brick, .	at	2	0
Rough Caſt, with ſingle fir Laths, no Scaffold outſide, . . .	at	2	2
Circular rough Caſt, with ditto,	at	2	10½
		Per Foot run.	
Quirks to wood Beads, . .	at	0	1
Circular Quirks to ditto, .	at	0	1½
Arris's to Groins, floated and ſet,	at	0	1
Arris to Stucco Groins, . . .	at	0	1½
Strait Bead and double Quirks,	at	0	4
Circular Bead and double Quirks,	at	0	6
		Per Foot Sup.	
Stucco Groins on Brick, .	at	0	4
Stucco Groins on ſingle fir Laths,	at	0	6
Circular Stucco to ſingle fir Laths to Backs of Nitches, &c. .	at	0	5
Spherical Stucco on ſingle fir Laths to Heads of Nitches, &c. .	at	0	8

		s.	d.
	Per Foot run.		
Strait Stucco Reveals to Windows, four Inches Face, . .	at	0	4
Circular Stucco Reveals of Windows, four Inches Face, . .	at	0	5
Strait Stucco Reveals to Windows, eight Inches Face, . . .	at	0	6
Circular Stucco Reveals ditto, .	at	0	8
	Per Inch on the Face run.		
Strait Soffits, . . .	at	0	1
Circular Soffits, . . .	at	0	1½
	Per Foot run.		
Plain Cornices, or Impoſt, under four Inches Girt, . . .	at	0	4
Circular plain Cornices, or Impoſt, do,	at	0	5

		s.	d.
	Per Inch Girt.		
Plain Cornices, or Impoſt, all above four Inches Girt, . . .	at	0	1
Circular ditto, . . .	at	0	1¼
All Angles to Cornices, above four in a Room, up to ſix Inches Girt, to be charged	each	1	0
Ditto above ſix Inches, up to a Foot, each		1	6
	Per Inch run.		
Plain Reed Moldings, . :	at	0	1½
Circular Reed Moldings, .	at	0	2
	Per Foot run.		
Hollow Members put up ſingle, up to one Inch Girt on the Face, or ſunk in deep to ſhow a Shade, . .	at	0	6
Circular ditto, ditto, .	at	0	8
Hollow Members put up ſingle, up to two Inches Girt on the Face,	at	0	8
Circular ditto, ditto, .	at	0	10½

		Per Foot run. s.	d.
Hollow Members put up ſingle, up to three Inches Girt on the Face,	at	1	0
Circular ditto, ditto, .	at	1	4
Hollow Members put up ſingle, four Inches Girt on the Face, .	at	1	4
Circular ditto, ditto, .	at	1	9
	Per Inch on the Face run.		
Strait enriched Soffits, . .	at	0	4
Circular ditto, ditto, .	at	0	5
Plain floated Grounds to frieze,	at	0	1
Circular ditto, ditto, .	at	0	1½
	Per Square. £.	s.	d.
Grey Plaſter Floors, two Inches thick, on ſingle fir Laths, in Town,	at 4	4	0
Red Plaſter Floors, two Inches thick, on ſingle fir Laths, in Town,	at 5	5	0

	Per Yard. s.	d.
Waſhing and ſtopping, . . at	0	1½
Waſh, ſtop, and White to new Work, at	0	1½
Waſh, ſtop, and White to old Work, at	0	2
Waſh, ſtop, and White in Diſtemper, at	0	6
Waſh, ſtop, and Lime White, . at	0	2
Waſh, ſtop, and Common Colour, at	0	3½
Waſh, ſtop, and Straw Colour, . at	0	5
Waſh, ſtop, and Buff Colour, . at	0	6
Waſh, ſtop, and Lemon Colour, at	0	6
Waſh, ſtop, and Grey Colour, . at	0	7
Waſh, ſtop, and Blue Colour, . at	1	2
Waſh, ſtop, and Pea Green, with Verditter, ... at	1	2

	Per Foot run. s.	d.
Waſh, ſtop, plain cornice for painters, &c. up to a Foot Girt, . . at	0	0½
Waſh, ſtop, and White plain Cornices up to a Foot Girt, with Common White, ... at	0	1
Waſh, ſtop, and White plain Cornices up to a Foot Girt in Diſtemper, at	0	1½
Waſh, ſtop, and White enriched Cornice, with two Members up to a Foot Girt, with Common White, . at	0	1½
Waſh, ſtop, and White Cornice, with two Members up to a Foot Girt, in Diſtemper, . . . at	0	2½
Waſh, ſtop, and White enriched Cornice, with two Members, and enriched Soffite, with Common White up to a Foot Girt, ... at	0	2

	Per Foot run. s.	d.
Waſh, ſtop, and White enriched Cornice, with two Members, and enriched Soffite, up to a Foot Girt, in Diſtemper, at	0	3
Waſh, ſtop, and White plain Ionick Block Cornice, up to a Foot Girt, with Common White, . . at	0	1½
Waſh, ſtop, and White plain Ionick Block Cornice, up to a Foot, in Diſtemper, ... at	0	2½
Waſh, ſtop, and White enriched Ionick Block Cornice, up to a Foot Girt, with Common White, . . at	0	2½
Waſh, ſtop, and White enriched Ionick Block Cornice, up to a Foot Girt, in Diſtemper, . . . at	0	3½
Waſh, ſtop, and White enriched Corinthian Block Cornice, up to a Foot Girt, with Common White, . at	0	4

	Per Foot run. s.	d.
Waſh, ſtop, and White enriched Corinthian Block Cornice, up to a Foot Girt, in Diſtemper, . . . at	0	6

	Per Foot Sup.	
Waſh, ſtop, and White to Ornaments, with Common White, . at	0	2
Waſh, ſtop, and White to Ornaments, in Diſtemper, . . . at	0	3

	Per Inch on the Face, Per Foot run.	
Picking out to Grounds of either Hollow or ſolid Members any Colour, at	0	1
Picking out to Friezes, or Soffits, at	0	1½

PRICES OF DAY-WORK

WINTER AND SUMMER.

		s.	d.	
Plafterer,	at	4	0	per Day.
Labourer,	at	2	9	ditto.
Boy,	at	1	4	ditto.
Laths and Nails,	at	2	9	per Bundle.
Lime and Hair,	at	0	10	per Hod.
Outfide Lime and Hair,	at	1	0	ditto.
Fine Stuff,	at	1	2	ditto.
Putty,	at	2	0	ditto.
Stucco,	at	2	6	ditto.
Plafter,	at	1	6	per Bag.

☞ That no Patches be meafured in future.

FINIS.